# User acceptance of vacuum toilets and grey water systems in The Netherlands, Norway and Germany

#### Authors:

Paul Telkamp, Adriaan Mels, Joost van den Bulk, Erwin Koetse and Okke Braadbaart

Sanitation Challenge, Wageningen, 19 May 2008

Corresponding authors (email):

Adriaan.Mels@wur.nl, paul.telkamp@tauw.nl





## Content of presentation

- Research results into user acceptance
  - Vacuum toilets
  - Grey water systems
- 5 projects
  - The Netherlands
  - Norway
  - Germany







## Introduction

Increasing interest

 Changes in households due to different working principles

User acceptance key issue





### Introduction

Separation of black and grey water

Vacuum toilets

Decentralized grey water systems





# Overview projects

Project (year of realization)	Short description
<b>Kaja</b> – Ås, Norway (1996)	24 student apartments equipped with a vacuum toilet system and a local grey water treatment system (biofilter + constructed wetland).
<b>Torvetua</b> – Bergen, Norway (1997)	40 single houses equipped with a vacuum toilet system and two local grey water treatment systems (biofilter + constructed wetland).
Wohnen&Arbeiten - Freiburg, Germany (1999)	14 apartments and 4 offices equipped with a vacuum toilet system and a membrane filter system for grey water treatment
Flintenbreite – Lübeck, Germany (2000)	30 houses equipped with a vacuum toilet system and two local grey water treatment systems (constructed wetlands).
Casa Vita – Deventer, The Netherlands (2007)	32 new apartments equipped with a vacuum toilet system, no local grey water treatment












#### Method interviews

- Standardized interview
  - household descriptors
  - invisibility
  - user comfort
  - robustness




- 20 households, except for Wohnen & Arbeiten
- October 2005 December 2007





#### Results interviews

Satisfaction of households with their vacuum toilet systems








#### Results interviews

#### Average marks given by the households








#### Results interviews

Percentage of households that considers the flushing sound of their toilet unpleasant







#### Sound level measurements

- Casa Vita and Lemmerweg-Oost in Sneek, The Netherlands
- Different types/brands of vacuum toilets
  - Casa Vita (manufacturer Jets)
  - Lemmerweg-Oost (manufacturer Roediger)
  - Three other vacuum toilets
    - Jets (same type as in Deventer)
    - Evac
    - Roediger with silencer







#### Sound level measurements


Lid open and closed

- Two conventional water flushing toilets
  - One standard flushing toilet
  - One shelf toilet ("Dutch toilet")





#### Method sound level measurements







Results in dB(A)	Lid	Maximal decibel production after correction for the reflections
Deventer (Casa Vita), Jets	closed	91
	open	95
Sneek, Roediger	closed	102
	open	104
Sneek, Evac	closed	93
	open	97
Sneek, Jets	closed	95
	open	99
Sneek, Roediger + silencer	closed	89
	open	93
Conventional Dutch toilet	closed	80
	open	87
Conventional toilet	closed	83
	open	85
Average results	Average decibel production after	
Vacuum toilet: average with	correction for the reflections  96 +/- 5	
standard deviation		
Conventional toilet: average with standard deviation	84 +/- 3	





Results in dB(A)	Lid	Maximal decibel production after correction for the reflections	
Deventer (Casa Vita), Jets	closed	91	Ì
	open	95	
Sneek, Roediger	closed	102	
	open	104	
Sneek, Evac	closed	93	\
	open	97	5
Sneek, Jets	closed	95	17/
	open	99	5 /
Sneek, Roediger + silencer	closed	89	7/
	open	93	ک
Conventional Dutch toilet	closed	80	
	open	87	
Conventional toilet	closed	83	
	open	85	
Average results	Average decibel production after correction for the reflections		
Vacuum toilet: average with standard deviation	96 +/- 5		
Conventional toilet: average with standard deviation	84 +/- 3		



 $\Delta 4 dB$ 



Results in dB(A)	Lid	Maximal decibel production after correction for the reflections
Deventer (Casa Vita), Jets	closed	91
	open	95
Sneek, Roediger	closed	102
	open	104
Sneek, Evac	closed	93
	open	97
Sneek, Jets	closed	95
	open	99
Sneek, Roediger + silencer	closed	89
	open	93
Conventional Dutch toilet	closed	80
	open	87
Conventional toilet	closed	83
	open	85
Average results	Average decibel production after correction for the reflections	
Vacuum toilet: average with standard deviation	96 +/- 5	
Conventional toilet: average with standard deviation	84 +/- 3	










Results in dB(A)	Lid	Maximal decibel production after correction for the reflections
Deventer (Casa Vita), Jets	closed	91
	open	95
Sneek, Roediger	closed	102
	open	104
Sneek, Evac	closed	93
	open	97
Sneek, Jets	closed	95
	open	99
Sneek, Roediger + silencer	closed	89
	open	93
Conventional Dutch toilet	closed	80
	open	87
Conventional toilet	closed	83
	open	85
Average results	Average decibel production after correction for the reflections	
Vacuum toilet: average with standard deviation	96 +/- 5	
Conventional toilet: average with standard deviation	84	1 +/- 3



**Silencer** 

11 – 13 dB ↓





Results in dB(A)	Lid	Maximal decibel production after correction for the reflections
Deventer (Casa Vita), Jets	closed open	91
Sneek, Roediger	closed open	102 104
Sneek, Evac	closed open	93 97
Sneek, Jets	closed open	95 99
Sneek, Roediger + silencer	closed open	89 93
Conventional Dutch toilet	closed	80 87
Conventional toilet	closed open	83 85
Average results	Average decibel production after correction for the reflections	
Vacuum toilet: average with standard deviation	96 +/- 5	
Conventional toilet: average with standard deviation	84	1 +/- 3



**Silencer** 


11 – 13 dB ↓





## Other possible improvements

- Optimisation of:
  - pipe dimensions
  - piping of the system
  - valves of vacuum toiletbackplate







#### Conclusions

- High appreciation of the grey water treatment systems (7.1 – 8)
- Average lower satisfaction level for vacuum toilets
- Appreciation generally high
- 40 65% considers the sound unpleasant vs. 25% of the control group





#### Conclusions

- Maximum sound level is 10 -12 dB louder
- To increase acceptance sound production has to be reduced
  - Optimisation pipe diameters/piping system
  - Optimisation of valve / backplate





#### Outlook

Sound level 

 more attention of the manufacturers

 Results in user acceptance and operational functioning will be continued

 Tauw has installed energy meters and logs possible blockages/failures





## Acknowledgement

This study was supported by the European Commission through the 6<sup>th</sup> Framework Integrated Project SWITCH (Sustainable Water management Improving Tomorrow's Cities' Health)





## Questions??

